

6.0 SCHEDULE

The milestones for clean closure are:

- Completion of the CEQA process;
- Regulatory approval of this Work Plan;
- Preparation of bid documents (e.g., design drawings and specifications);
- Completion of contracting and selection of a Contractor;
- Completion of construction and confirmation sampling and analysis;
- Site restoration (e.g., final grading and re-vegetation);
- Certification of clean closure;
- Completion of groundwater monitoring and rescission of the WDRs.

6.1 Project Schedule

The general anticipated schedule for the clean closure project is provided in Appendix G.

6.2 Winterization Contingency

It is possible, although unlikely, that Site construction may span more than one dry season, and therefore, waste could potentially be freshly exposed during the rainy season. If necessary, the Contractor will prepare a Winterization Plan for review and approval by the project engineer prior to the beginning of each rainy season. The Winterization Plan will be required until all waste is removed and excavation areas are fully restored with vegetation. This plan will detail storm water erosion and sedimentation controls, wind erosion controls, the placement of interim cover to prevent human exposure to waste and storm water contamination, and Site security measures. The plan will also address periodic inspection and maintenance of the winterization controls.